

US 36 Project Status

District	Project	County	Route	Direction	Begin Log	End Log	Estimated Letting Date	Estimated Completion Date	Location	Description
1	J1P0913	Caldwell	36	W	133.254	146.419	2008	Dec. 2008	on westbound lane from east of Rte 13 to Livingston County	Resurface driving lanes and shoulders
1	J1P0975	DeKalb/Buchanan	36	W	176.8	180.984	August-06	Dec. 2007	from Rte 31 west to Rte 31 east near Stewartsville	Microsurface westbound lanes
1	J1P0924	Buchanan	36	W	5.908	11.742	November-06	Dec. 2007	from 0.75 mile east of Rte AC to Rte 31 south, near St. Joseph	Resurface westbound lanes with 1 3/4 inches asphalt
1	J1P0876	DeKalb	36	E	26.984	28.587	December-06	Dec. 2007	from 0.2 mile west of Rte 33 north to 1.4 miles east of Rte 33 north near Cameron	Resurface eastbound lane pavement with 3 3/4 inch asphalt
1	J1P0876	DeKalb	36	W	164.127	165.737	December-06	Dec. 2007	from 0.2 mile west of Rte. 33 north to 1.4 miles east of Rte. 33 north near Cameron.	Resurface westbound lane pavement with 3 3/4" asphalt
1	J1P0920	DeKalb	36	E	27.184	31.943	December-06	Dec. 2007	from Rte 33 north to west of Bus 36 near Cameron	Resurface westbound lane pavement with 3 3/4 inch asphalt
1	J1P0970	Buchanan	36	E	0.332	0.547	March-07	Dec. 2007	0.2 mile east of the Missouri River in St. Joseph	Replace expansion joints
1	J1P0971	Buchanan	36	E	0	0.04	March-07	Dec. 2007	on Pony Express Bridge over the Missouri River, in St. Joseph	Replace expansion joints
1	J1P0971	Buchanan	36	W	192.614	192.709	March-07	Dec. 2007	on Pony Express Bridge over the Missouri River, in St. Joseph	Replace expansion joints
1	J1P1008	Buchanan	36	E	0	0.133	March-07	Dec. 2007	on eastbound and westbound bridges east of the Missouri River near Kansas State line.	Replace expansion joints
1	J1P1008	Buchanan	36	W	192.381	192.461	March-07	Dec. 2007	on eastbound and westbound bridges east of the Missouri River near Kansas State line.	Replace expansion joints
1	J1P0921	DeKalb	36	E	17.427	27.832	April-07	Dec. 2007	from 1.5 miles east of Rte 31 (north) to Rte 33 (north), near Stewartsville	Resurface eastbound lanes and shoulders with 5 inches of asphalt
1	J1P1034	Caldwell	36	E	35.861	46.599	to be determined		from east of DeKalb County to Rte 13 Hamilton	Resurface eastbound lanes and shoulders
1	J1P1036	DeKalb	36	E	165.537	176.3	to be determined		from east of Rte 31 to Rte 33 near Stewartsville	Resurface eastbound lanes and shoulders
2	J2P0733	Livingston	36	E	72.854	95.901	November-06		from 1.0 mile east of Rte 65 to 0.7 mile east of Brookfield	Resurface to provide smoother pavement and rehabilitate bridges
2	J2P0733	Linn	36	W	93.927	119.845	November-06		from 1.0 mile east of Rte 65 to 0.7 mile east of Brookfield	Resurface to provide smoother pavement and rehabilitate bridges

2	J2P0750	Linn	36	E	95.508	108.99	January-07		from 2 miles west of Rte 11 south to Macon County line	Resurface pavement and rehabilitate bridges to provide smoother pavement
2	J2P0750	Linn	36	W	86.741	87.98	January-07		from 2 miles west of Rte 11 south to Macon County line	Resurface pavement and rehabilitate bridges to provide smoother pavement
2	J2P0769	Macon	36	E	123.002	131.014	January-07		from Middle Fork Chariton River to end of dual lanes east of Macon	Diamond grind and overlay pavement to provide smoother pavement and rehabilitate bridges
2	J2P0769	Macon	36	W	61.662	69.683	January-07		from Middle Fork Chariton River to end of dual lanes east of Macon	Diamond grind and overlay pavement to provide smoother pavement and rehabilitate bridges
2	J2P0751	Livingston	36	E	66.084	66.86	February-07		from Caldwell County line to Rte 65 in Chillicothe	Resurface pavement to provide smoother pavement
2	J2P0751	Livingston	36	W	121.843	133.226	February-07		from Caldwell County line to Rte 65 in Chillicothe	Resurface pavement to provide smoother pavement
2	J2P0482	Macon	36	E	131.082	153.283	October-07	December-09	from end of divided lanes east of Macon to Shelbina	Earthwork and paving for dual lanes
2	J2P0482	Shelby	36	W	39.395	61.594	October-07	December-09	from end of divided lanes east of Macon to Shelbina	Earthwork and paving for dual lanes
2	J2P0772	Macon	36	E	131.014	139.506	October-09	December-10	from Kellogg Street to Shelby County line	Resurfacing of existing pavement to provide smoother pavement
2	J2P0772	Macon	36	W	53.172	61.662	October-09	December-10	from Kellogg Street to Shelby County line	Resurfacing of existing pavement to provide smoother pavement
3	J3P0412B	Marion	24	E	186.156	192.737	August-06	September-08	from 0.2 mile east of Ralls County line to 0.9 mile west of Rte 24/36 interchange	Grading and paving for dual divided
3	J3P0411B	Marion	36	E	171.652	176.641	August-06	September-08	from 0.4 mile west of Rts Z to 0.2 mile east of Marion County	Grading and paving for dual divided
3	J3P0715	Marion	36	E	185.917	187.881	May-07	October-07	from east of Shinn Lane to new concrete pavement	Pavement improvements on eastbound concrete pavement
3	J3P0409C	Marion/Shelby	36	W	27.576	39.38	August-07	December-09	from 0.6 mile west of Rte 15 east to 0.1 mile east of Marion County line	Grading and paving for adding lanes
3	J3P0410	Marion	36	W	20.905	27.552	August-07	December-09	from Shelby County to 0.4 miles west of Ralls County	Grading and paving for adding lanes
3	J3P0785	Ralls/Marion	24	E	183.783	192.686	Future	Dec. 2011 or 2012	from 1.1 miles west of Rte J in Ralls County east to 0.9 miles east of Rte H in Marion County	Resurface pavement to provide smoother pavement